BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16558

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Providing pathway and other development works to Ganesha layout park in MS Palya ward no. 11

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GANGADHAR H	
				In Figures	In Words
1	1220.68	KSRB 2-2.1 : Earthwork in surface excavation in oridinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavted surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	145.00	Rupees One Hundred Forty Five Only
2	84.74	earth work excavation for foundation of building, water supply, sanitary lines and electrical conditions either in pits or in trenches 1.5m and above in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the escavated soil clean from edges of excavation with lead upto 50m after breaking of complete as per specifications	Cum	260.00	Rupees Two Hundred Sixty Only
3	1297	Lead for Disposal of Debris/earth shall be payable at garage rates by Mechanical means including loading and unloading from 14Kms to 15Kms	Cum	105.00	Rupees One Hundred Five Only
4	1737	Providing and fixing precast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete -do- size 450 x150 x 500mm	Nos	350.00	Rupees Three Hundred Fifty Only
5	1083.9	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kgs per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand undermeath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specification	Sqm	883.00	Rupees Eight Hundred Eighty Three Only
6	6	Providing and fabricating, supplying and erecting to plumb and line MS grill work as per approved design and drawing using 50x50x6mm angle of heavy gauge as support and 35x35x6mm angles of heavy gauge for frame work with 100x50mm channel section to join grills 16mm and 10mm square rods are used for verticals at 75mm c/c alternatively, 35x35x6mm equal angle to be provided horizontally 2nos at top and 2 at bottom (4nos) as shown in drawing. The work is inclusive of thoughing angels, square rods, and angles, square rods and angels and channel welding to suitable size for each bay. All the joints are welded together including grinding, finishing, metal patti and painting two coats of anticorrosive paint over one coat of primer. The set is inclusive of all materials like MS angles, hold fast, cost of labhour for all items of work. cost of painting, welding, cutting, lathe work, grinding, thoughing including loading and unloading with all lead and lift charges etc., complete	Sqm	4540.00	Rupees Four Thousand Five Hundred Forty Only
7	273.58	Providing and applying ready mix priming coat over concrete/masonry /asbestos cement sheet plastered surfaces including preparing the surface after through brooming of oil,grease,dirt and other foreign matter,and sand papering including cost of materials, labhour, complete as per specifications	Sqm	23.00	Rupees Twenty Three Only
8	273.58	Providing and applying painting with ready mix paint in two coats(excluding priming coat) over new concrete/asbestos cement sheet/plastered surface brush to give an even shade after preparing the surface after through brooming of oil, dirt, and other foreign matter and sand papering including cost of materials, labhour, complete as per specifications.	Sqm	45.00	Rupees Forty Five Only
9	2	Providing and fixing dust bins as per designs, drawing specification and direction of Engineer in charge of works	Nos	4780.00	Rupees Four Thousand Seven Hundred Eighty Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/03

25/03